

QUALITY TEST REPORT

CUSTOMER	-	REQUESTED BY	Sales	WRITTEN	REVIEWD	APPROVED
MODEL	BHB20LED		SOO	INTERNALLY PASSED		
PART NAME	ASS'Y	COL/VER	BK			
TEST DATE	2016-06-28	REPORT DATE	2016-06-28	RESULT	PASS	
CLASS	Sample	WRITTEN BY	QC TEAM / Man Wook Han			
TEST NAME	IP 69K			LOT NO.		
PURPOSE	RELIABILITY ASSURANCE OF NEW DEVELOPED PRODUCT					
TEST METHOD	30 SEC. FOR EACH NOZZLE / TEMP : -5~+80℃ / FLOW : 14~16L/Min PRESSURE : 80~100 bar / DISTANCE : 5~10Cm / ANGLE : 0°, 40° 60°, 90° PRODUCT IS SITTING ON TURNTABLE, ROTATING 5rpm					
CRITERION	NO PHENOMENON SUCH AS MOISTURE, WATER DROP AND PERCOLATED WATER IS TO BE OBSERVED					
TEST RESULT	PASS					
REMARK	-					

▣ TEST PROCCESS (PICTURES)



QUALITY TEST REPORT

CUSTOMER	-	REQUESTED BY	Sales	WRITTEN	REVIEWD	APPROVED
MODEL	BHB20LED		SOO	INTERNALLY PASSED		
PART NAME	ASS'Y	COL/VER	BK			
TEST DATE	2016-06-28	REPORT DATE	2016-06-28	RESULT	PASS	
CLASS	Sample	WRITTEN BY	QC TEAM / Man Wook Han			
TEST NAME	WATER PROOF (IP68)			LOT NO.		
PURPOSE	RELIABILITY ASSURANCE OF NEW DEVELOPED PRODUCT					
TEST METHOD	POWER THE PRODUCT ON FOR 1HR, MAKING THE HOUSING HEATED PUT THE PRODUCT ON THE TUB FOR 30 MINTS AND SEE ANY WATER PASSED THROUGH					
CRITERION	NO PHENOMENON SUCH AS MOISTURE, WATER DROP AND PERCOLATED WATER IS TO BE OBSERVED					
TEST RESULT	PASS					
REMARK						

▣ TEST PROCCESS (PICTURES)

